

# **Upgrading a Set of Large Cooling Water Pumps with the Aim to Increase Capacity at Least 13 Percent and Minimize Impeller Cavitation**

Frank Visser

Flowserve FSG Pumps

Case Study

27<sup>TH</sup> International Pump Users Symposium, Houston, Texas, USA  
September 12 – 15, 2011

## Contents



- Background
- In-situ capacity measurement
- Impeller-diffuser CFD study
- Scaled model testing
- Start-up transient
- As built performance

## Background

- Up-rate of Nuclear Power Station.
- Increase of electrical output power required increase of cooling water capacity (> 13%).
- Existing cooling water pumps (CWPs) are suffering from cavitation attack.
- CWP retrofit design objective:
  - Cooling water capacity increase of 13%+
  - Minimize impeller cavitation
- CWP E-motor replacement ( $P_{CWP} \uparrow$ )
  - System start-up transient analysis

## Background

Four (4) CWP running in parallel feeding condenser with seawater



## In-Situ Cooling Water Capacity Measurement


- Required to establish pre-upgrade baseline situation
  - Total CWP's flow rate measurement
  - Individual CWP's head measurement
- Flow rate measurement with OTT-mills
  - 6 mills on a horizontal scanning bar
  - 4 throughflow areas scanned (curtain wall)
  - 6x14 scanning window (14 elevations)



## In-Situ Cooling Water Capacity Measurement



## In-Situ Cooling Water Capacity Measurement



	Existing				Up-rate			
Speed	325		r/min		325		r/min	
Capacity	7.8	m <sup>3</sup> /s	275	cfs	> 8.81	m <sup>3</sup> /s	> 311	cfs
Head	5.7	m	18.7	ft	> 7.3*	m	> 24.0	ft
$N_{s,D}$	12700 4.64		rpm, gpm, ft (-)		11200 4.1		rpm, gpm, ft (-)	
$D_{nom}$	56"				58" – 59"			

\* Per quadratic scaling


## Impeller-Diffuser CFD Study

- Geometries studied:
  - Existing impeller / diffuser combination
  - Retrofit impeller / diffuser combination
- Objective
  - Determination of best cavitation point (BCP) → NPSHi
  - Evaluate cavitation development
  - Head comparison

Note: Both the existing and retrofit design have 4 impeller blades / 7 diffuser blades


# Impeller-Diffuser CFD Study

## Existing Design




# Impeller-Diffuser CFD Study


## New Design for Upgrade



## Impeller-Diffuser CFD Study





## Impeller-Diffuser CFD Study






## Scaled Model Testing

- Objective
  - Verify hydraulic performance
- Scaled model testing
  - 1:4 model scale (approx. 14" test impeller)
  - 4:1 speed ratio (approx. 1300 r/min)
  - Existing impeller-diffuser
  - Up-rate impeller-diffuser
- Existing parts reproduced on scale from 3D Faro-arm scan
- Up-rate hydraulic parts modeled directly in 3D CAD



## Scaled Model Testing

- Test Loop & Test Set-up
  - Q, H,  $\eta$  performance testing
  - Cavitation visualization





Flow visualization window  
with impeller mounted


## Scaled Model Testing

Cavitation @ 90% duty capacity:

- Experiment
- CFD




# Scaled Model Testing



## Start-Up Transient

- Objective:
  - Check motor capability (torque) to start the pumps
  - Determine start-up time(s)
- Entire cooling water system is modeled




## Start-Up Transient


- Start-up requirement E-motor:
  - 80% Voltage
  - -15% Torque (tolerance per IEC 60034-1)
- Start-up scenario:
  - P1 thru P4 are started at 60 sec intervals
- Initially selected motor showed problem when starting 4<sup>th</sup> pump
  - P4 could not be accelerated to full speed due to insufficient motor torque
  - P4 ended up running against closed (check) valve at intermediate speed

## Start-Up Transient

Pump curve




Motor speed-torque curve  
(80% Voltage; -15% Torque)




# Start-Up Transient


Speed Torque Pump 1 (-15% Tol)




Speed Torque Pump 2 (-15% Tol)



Speed Torque Pump 3 (-15% Tol)




Speed Torque Pump 4 (-15% Tol)




## Start-Up Transient

- Issue solved by new motor with better speed-torque



Cooling water flow through condenser at start-up


## As Built Performance



- Final design built @ 58 1/16"
- Taking into account:
  - Performance pick-up due to up-scaling
  - Intake & discharge losses not being accounted for in impeller/diffuser CFD study and scaled model testing
  - System resistance line was lowered due to installing power pack (actuator) on check valves → less steep characteristic
  - Contractually required capacity increase of 113%, with +3% tolerance.

## As Built Performance

- In-situ field performance check
  - Four pumps running
  - Three pumps running
- Pumps are over-performing (Q-H)
  - Pump Q-H above predicted curve
  - System resistance curve lowered more than expected
  - Higher condenser cooling capacity
  - Higher driver power, but motors are not overloaded
- At the end: Everybody Happy!



**Thank you for your attention**